KOLAR DIVISION.

Notification, dated 29th May 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 p.m. on 3rd July 1933, for the work of restoring Lakshmisagara Kodagikere, Reg. No. 203—647 of Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th June 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed. Rates should be written both in words and figures, otherwise tenders will not be accepted.

4. Each tender must be accompanied by a deposit of Rupees one hundred and twenty in cash or Government Promissory Notes, as earnest money and be superscribed "Tender, for the work of restoring Lakshmisagara Kodigikere, Reg. No. 203—647 of Malur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason what ever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for restoring Lakshmisagara, Kodagikere Reg. No. 203—647, of Malur Taluk.

No.	Items of work	Unit	Rate	Quatity	Cost
	Bund at R. L. 54·50 4½ feet width.		Rs. a. p.		Rs.
1	Jungle clearing including Picking top soil	Grade	3 0 0	20	60
2	Removing ant hills and filling them with sand.	Each	0 8 0	8	4
3	Cutting and removing big trees ..	„	1 0 0	20	20
4	Cutting grips	Grade	2 0 0	20	40
5	Earth-work with consolidation ...	C.yd.	0 4 0	950	238
6	Turfing the slopes of Bund	S.yd.	0 1 0	3,852	241
7	Constructing new stone work Revetment...	C.yd.	1 14 0	335	628
8	Removing and resetting old stone revetment	„	0 12 0	295	221
9	Providing and fixing new grade stones including painting, etc.	Each	1 8 0	20	30
10	Index stones do	„	0 8 0	20	10
11	Register No. and date stone, painting, etc.	„	5 0 0	1	5
12	B. M. stones do ..	„	5 0 0	2	10
13	Gauge stone ..	„	15 0 0	1	15
	Total for bund ...		...		1,522—
	Sluice at R. L. 42·00				
1	Earth-work excavation for foundation ...	C yd.	0 3 0	55	10
2	Refilling earth with consolidation as per above excavation.	...	0 3 0	55	10
3	Stone jelly concrete in surki mortar ...	C.ft.	0 4 0	120	30
4	Burnt brick in surki mortar ...	„	0 4 0	167	42
5	Burnt stone slabs ...	S.ft.	0 6 0	98	37
6	Plastering with surki mortar ...	„	4 0 0	201	8
7	Providing teak-wood plug with iron rod and with locking arrangements.	Each	15 0 0	1	15

No	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
8	Drilling holes in slabs ...	Each	0 12 0	8	6
9	Dismantling old sluice ...	Lump-sum	...	...	25
10	Providing 4" Diameter (C. I. pipes with 6" fall).	R.ft.	2 0 0	36	72
	Total for sluice ...		...		255
	Waste Weir 125' long.				
1	Earth-work excavation for foundation ...	C.yd.	0 3 0	47	9
2	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 0	286	72
3	Dismantling the existing body to a depth of 3'.	"	0 0 6	9	1
4	Burnt-brick in surki mortar ..	"	0 5 0	311	97
5	Burnt-stone slabs 6" thick, dressed and fixed.	S.ft.	0 6 0	512	192
6	Refixing old available slabs ...	"	0 1 0	42	3
7	Plastering with surki mortar ..	Sqr.	4 0 0	526	21
8	Dismantling the old existing apron	C.yd.	0 8 0	12	6
9	Constructing new rough stone apron ...	"	1 14 0	58	109
10	Constructing old stone apron with available stone.	"	0 12 0	12	9
11	Providing joggle joints ...	Each	0 8 0	25	12
	Total for waste weir ...		...		531
	Grand Total ...			1522+255+531=2,308	

Notification, dated 29th May 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 4th July 1933, for the work of restoring Kusandra Balayankunte Regd. No. 253 of Srinivaspur Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th June 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. Rates should be expressed in words and figures; otherwise, the tender will not be accepted.

4. Each tender must be accompanied by a deposit of Rupees one hundred and forty only in cash or Government Pomissory Notes, as earnest money, and be superscribed "Tender for the work of restoring Kusandra Balayankunte Regd. No. 253 of Srinivaspur Taluk, in default of which tender will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for retoring Kusandra Balayankunte, Register No. 253, Serial No. 200 of Srinivaspur.

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund R. L. 55·00.		Rs. a. p.		
1	Earthwork to bund watering and tamping including lead and lift to R. L. 55·00.	Cyd.	0 4 0	5,133	1,283
2	Earthwork to breach watering and tamping	„	0 5 0	531	166
3	Turfing to bund	Syd.	0 1 0	4,977	311
4	Providing new grade stones with figuring and painting etc., complete.	Each	1 8 0	15	23
5	Do Index stones ...	„	0 8 0	15	7
6	Do Date and Regd. No. stones	„	4 0 0	1	4
7	Do Gauge stones ..	„	15 0 0	1	15
8	Do Bench mark stones ..	„	3 0 0	191	119
9	Puddle wall mixed with good gravel ...	Cyd.	0 10 0	191	119
10	Jungle clearing and removing roots and ant hills.	Lump	sum	...	75
11	Earthwork excavation for corewall in breach.	Cyd.	0 4 0	24	6
12	Surki concrete for foundation ...	Cft.	0 4 6	238	66
13	Burnt brick in surki mortar for corewall ..	„	0 4 6	646	182
	Total ...	...	...	...	2,263
	Sluice R. L. 45·00.		Rs. a. p.		
1	Earthwork excavation in bund to construct Sluice.	Cyd.	0 3 6	61	13
2	Refitting the same with watering, etc., ..	„	0 3 6	53	11
3	Surki concrete for foundation	Cft.	0 4 6	270	76
4	Burnt brick in surki mortar	„	0 4 6	193	54
5	Burnt stone slabs 6" thick fixed with mortar.	Sft.	0 6 0	206	77
6	Plastering with surki mortar	Sqr.	3 8 0	2·76	10
7	Providing wooden plug with iron rod and locking arrangements.	Lump	sum	..	15
8	Cutting holes in cross and orifice slab ...	Each	1 0 0	3	3
	Total ...	...	...	...	259
	Waste Weir R. L. 50·00.				
9	Earthwork excavation for bodywall & returns.	Cyd.	0 4 0	78	20
10	Surki concrete for foundation	Cft.	0 4 6	216	61
11	Rough stone in surki mortar	„	0 5 0	314	98
12	Burnt stone slabs 6" thick fixed with surki mortar.	Sft.	0 6 0	149	56
13	Pointing in cement mortar	Sqr.	4 8 0	4·00	18
14	Rough stone work for apron	Cyd.	1 12 0	42	73
	Total ...	...	...	...	326
	Grand Total Rs. 2263+259+326—Rs. 2,848				

C. T. NARASIMHA IYENGAR,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification, dated 26th May 1933.

The attention of the Public is invited to the detailed notification calling for tenders for restoring Dodchikonahally Hosakere Minor Tank, Regd. No. 42 of Nagamangala Taluk, published in pages 632 and 633, part VI of the *Mysore Gazette*, dated 1st June 1933 date upto tenders will be received is 19th June 1933 till 12 noon.

K. NARAYANA IYENGAR,
Executive Engineer.